

Contractor Bid Request

November 8, 2022

Homeowner Name: Richard XX

Project Address: XX Fremont, CA 94538

Homeowner Contact: XX

Structure Type: MH Single Bid Due Date: 11/21/22

Project Description: Windows, door, floor

This Scope of Work was developed by a Habitat for Humanity Inspector based upon an inspection of the property. Items are listed in order of their priority. Contractors must provide an itemized estimate for each item listed below. The selected contractor will be required to provide proof of current license, insurance and workman's comp and submit a completed W-9 in advance of starting the project. Project address and homeowner phone number available upon request.

Any questions or requested modifications should be directed to: XX

Priority A: Required items, including code violations and health and safety issues. <u>These items must be completed prior to consideration of general, non-essential property improvements.</u>

Priority B: General property improvements. Items to be completed if budget allows.

Priority	Priority	Item Description
Letter	Number	
Α	1	Replace skirting around mobile home. Update with new, standard
		skirting cut to fit contour of ground. Close off under mh area to
		stop critters from getting in. Follow industry standard and remove
		debris.
Α	2	Replace Flooring: Remove and replace flooring in the hall. a.
		Demo and repair all damaged, rotted or loose sub-floor and install
		appropriate under-layment where needed. b. Install new flooring
		as specified (vinyl plank flooring.) Work will include installation of
		primed and painted baseboard or ¼ round to match existing trim
		and all required transitions
		Dispose of debris.
Α	3	Replace total of 4 windows on the carport side of the house.
		Window type and dimensions to match existing. All new windows
		must meet the energy performance standards of California's
		Energy Code. a. Make all measurements for accurate install and
		recommend best solution to work with existing interior and

		exterior conditions. b. Install replacement type PVC window with
		fusion welded frame. Should be double pane, low E glass with
		Argon insulation layer. 0.35 U factor. c. Install new window
		sash(es). Work will include planning, equipment and material
		acquisition, area prep and protection, setup and cleanup. Special
		conditions include: *Work to be permitted and inspected.
Α	4	Replace Existing Sliding Door - total of 1. Special conditions
		include: Door type and dimensions to match existing. All new
		sliding doors must meet the energy performance standards of
		California's Energy Code. Make all measurements for accurate
		install and recommend best solution to work with existing interior
		and exterior conditions. Install replacement type sliding door with
		fusion welded frame. Should be double pane, low E glass with
		Argon insulation layer. 0.35 U factor. Install new door panels.
		Work will include planning, equipment and material acquisition,
		area prep and protection, setup and cleanup. *Work to be
		permitted and inspected.
Α	5	Repair or replace garbage disposal in kitchen:
		Replace and update drain line, hoses, and valves under kitchen
		sink. Also replace kitchen sink faucet.

Exclusions: Any items not included in the above scope of work.





Scope of Items and Descriptions







